

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00554-00-00  
Spot: E2NENWSW Sec/Twnshp/Rge: 32-5S-20W  
2310 feet from S Section Line, 996 feet from W Section Line  
Lease Name: JOHNSON B Well #: 2  
County: PHILLIPS Total Vertical Depth: 3633 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3633		125 SX
SURF	10.75	175		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/19/2014 11:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: RIC HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 689-7567

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
Ran sand line down to 3550'  
Production perfs: 3600' - 3610'  
Casing leaks from 2579' - 2850' and 2952' - 3265'  
Squeezed at 2920' w/200 sx cement  
Squeezed from 178' - 800' w/200 sx cwc  
Squeezed from 2172' - 2202' w/100 sx cement

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/19/2014 5:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1125' and 1775'. Ran tubing to 3555' and pumped 200 sx cement w/300 # hulls. Pulled tubing to 1793' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1132' and pumped 80 sx cement w/100 # hulls. Pulled all tubing. Topped of 5 1/2" casing w/20 sx cement. Backside had cement to surface.

GPS: 39.57377N -099.60565W

Perfs:

Top	Bot	Thru	Comments
3600	3610		
3598	3620		

Remarks: SWIFT SERVICES TICKET # 25382

Plugged through: TBG

District: 04

Signed

Pat Bedore  
3/24/14 (TECHNICIAN)

KCC WICHITA

CM

MAR 03 2014

MAR 05 2014

Form CP-2/3

RECEIVED