

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20211-00-01  
Spot: NESENW Sec/Twnshp/Rge: 3-14S-19W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: ORTH E Well #: 3  
County: ELLIS Total Vertical Depth: 3887 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3885		150 SX
SURF	8.625	203		150 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/12/2014 9:00 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO Phone: (316) 267-3241

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Operator wanted all cement plug.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/12/2014 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 2050', 1474' and 770'.  
Ultimate ran in hole with tubing to 3450'. Quality rigged to tubing and pumped 150 sx cement w/200 # hulls mixed in. Pulled tubing to 1950'. Quality pumped 250 sx cement w/300 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing w/50 sx cement. Hole standing full. 8 5/8" instant pressure

GPS: 38.86622 -099.42055  
NE NE SE SW  
3629' FSL 2853' FEL

Perfs:

Top	Bot	Thru	Comments
3818	3826		
3669	3671		
3649	3651		
3647	3650		
3604	3606		
3603	3605		
3504	3506		

Remarks: QUALITY OILWELL CEMENTING TICKET # 477

Plugged through: TBG

District: 04

Signed

KCC WICHITA

MAR 18 2014

RECEIVED

(TECHNICIAN)

CM

MAR 12 2014