

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-001-03658-0000
 Spot: SWNE Sec 9 Twp 26 S Rng 18 ☒ E / ☐ W
4602 Feet from ☐ N / ☒ S Line of Section
1261 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 38.709750 Long: -95.43813762 Date: 9/6/12
 Lease Name: Mike Olson (Humboldt) Well #: JON 01
 County: Allen Total Vertical Depth: 810 feet

Operator License No: 101 String Size Depth Pulled Comments
 Op Name: STATE OF KANSAS DRIVE - Drive Pipe 8.000 20 0 EST
 Address 1: 130 S. MARKET T1 - Tubing 1 2.000 810 0 EST
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202 - _____

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 11/22/13 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: _____ Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: PART - Partial
 Date/Time Plugging Completed: 11/22/13 / _____ KCC Agent: Frank Guilfoyle
 Actual Plugging Report:

Clear location. Run 1" inside 2" to 800 ft. Run 1" outside 2" 775 ft. Wash inside 2" to 810 ft. Wash outside to 785 ft. Pump Portland cement from TD to surface inside 2" and outside 2" to surface. Pull pipe ant top off well. Pump total of 131 sacks of Portland cement. Well plugged.

Perfs: Top Bottom Thru

Remarks: Contract # 11782. Category II. Control # 20140031-001. GPS'ed by Ryan Duling. Reg. Section. NAD 83.

Plugged Thru: TBG - Tubing

RECEIVED
KANSAS CORPORATION COMMISSION

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

FEB 03 2014

CONSERVATION DIVISION
WICHITA, KS

(Technician)

Form: District Plugging Report - _____