

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 087 - 20970 - 0000 (of this well)

Operator's Full Name Mid-Continent Energy Corp.

Complete Address 120 Bldg., Suite 712, Wichita, Ks. 67202

Lease Name Gerdes Well No. 1

Location SE NE SW Sec. 7 Twp. 30s Rge. 11(E) (W) X

County Barber Total Depth 2850

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 10 Am. Day 10 Month 9 Year 1980

The above well was plugged as follows:

300' 8 5/8" casing w/225 sax cement. 4 1/2" casing set at 2849' w/125
sax cement. Plug back to 2811'-Pref's., at 2766-92'-Allied mixed &
pumped 35 sax common cement in 4 1/2" casing to 2575'-Pull 2230' casing.
Allied mixed & pumped 8 sax hulls-25 sax gel-150 sax 50/50 posmix
cement w/4% gel & 3% ccin 8 5/8" casing back to zero ft. Surface
pipe flowing salt water.

RECEIVED
STATE CORPORATION COMMISSION
7-12-80
SEP 12 1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged (as herein stated).

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 9-28-80
INV. NO. 3110-20