



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

MAR 31 1975  
3-31-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Braden-Deem Inc

Complete Address 200 E First Wichita, KS

Lease Name Davis Ranch Well No. 2-3

Location NW/SW/SE Sec. 3 Twp. 35 Rge. 15 (E) (W) W

County Barber Total Depth 4995

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Nicholas Casing Pulling

Address Box 373 Geneseo, KS License No. 711

Operation Completed: Hour 10:00 AM Day 26 Month 3 Year 1975

The above well was plugged as follows:

802 ft 8 5/8 surface cemented with 600 sacks. 4970 ft 4 1/2 long  
string cemented with 75 sacks. Top perf. 4914 ft. Sand to 4900 ft,  
4 sacks cement with bailer. Pulled 4500 ft 4 1/2. Set 10 ft rock  
bridge at 200 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 4/11/75

INV. NO. 1069-W