

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
MAR 31 1975
3-31-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Braden-Deem Inc

Complete Address 200 E First Wichita, KS

Lease Name Davis Ranch Well No. 1-3

Location NE/SE/NW Sec. 3 Twp. 35 Rge. 15 (E) (W) W

County Barber Total Depth 4962

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling

Address Box 373 Geneseo, KS License No. 711

Operation Completed: Hour 11:00 AM Day 26 Month 3 Year 1975

The above well was plugged as follows:

230 ft 13 3/8 surface cement circulated. 1121 ft 8 5/8 surface
cement circulated. 4961 ft 5 1/2 long string cemented with 100 sacks.

Top perf. 4866 ft. Sand to 4850 ft, 5 sacks cement with bailer.

Pulled 4123 ft 5 1/2. Set 10 ft rock bridge at 200 ft. Fill hole
with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4/1/75

INV. NO. 1068-W