

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1965
6-11-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name K & E Drilling, Inc.

Complete Address: 719 Union Center, Wichita, Kansas

Lease Name Davis Ranch Well No. # 2-1

Location Approx. C W/2 Sec. 1 Twp. 35 Rge. 15 (E) (W)W

County Barber Total Depth 4953'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: K & E Drilling, Inc.

Address: 719 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 3:30AM Day 10th Month June Year 1965

The Above well was plugged as follows:

120' of 13 3/8" conductor string, cement circulated. 826' of 8 5/8"
surface pipe, cemented with 125 sacks. Hole was filled with drilling mud
to 300', 1st cementing plug, bridged solid with dry cement and hulls on
fluid at 300', and cemented with 25 sacks. Hole was filled with drilling
mud to 40', 2nd cementing plug, bridged solid with dry cement and hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/11/65

INV. NO. 1299-4