

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1965
1-7565
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name K & E Drilling Inc.

Complete Address: 719 Union Center, Wichita, Kansas

Lease Name Davis Ranch Well No. # 2-9

Location Approx. C W/2 Sec. 9 Twp. 35 Rge. 15 (E) W

County Barber Total Depth 5210

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: K & E Drilling Inc.

Address: 719 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 12:30AM Day 21st Month Jan. Year 1964

The Above well was plugged as follows:

1061' of 8 5/8" surface pipe, cemented with 700 sacks. Hole was filled
with drilling mud to 300', 1st cementing plug, bridged solid with dry cem-
ent and hulls on fluid at 300', and cemented with 25 sacks. Hole was fill-
ed with drilling mud to 40', 2nd cementing plug, bridged solid with dry
cement and hulls on fluid at 40', and cemented with 10 sacks to the base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 1/26/65

INV. NO. 591-W

Signed: Archie Elving
Well Plugging Supervisor