

15-007-07320-0000

Form CP-3  
Rev. 6-26-62

14  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 9 1964

4-9-64

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Braden Drilling Inc.

Complete Address: 1620 Wichita Plaza, Wichita, Kansas

Lease Name Davis Ranch Well No. # 4-12

Location NW NE Sec. 12 Twp. 35 Rge. 15 (E) (W)W

County Barber Total Depth 4966

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:00PM Day 8th Month April Year 1964

The Above well was plugged as follows:

855' of 8 5/8" surface pipe, cement circulated. 4966' of 4 1/2" long  
string, cemented with 50 sacks. Plug back to 4951'. Top perferation  
4910'. Bottom of hole was sanded to 4900', and cemented with 3 sacks.  
Hole was filled with mud to 300', with 10' rock bridge, and cemented  
with 25 sacks. Hole was filled with mud to 40', with 10' rock bridge,  
and cemented with 10 sacks to base cellar.  
4508' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/9/64

INV. No. 8918-11