


 KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1965
 10-25-65
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Operator's Full Name K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name Davis Ranch Well No. # 2-6

Location C NE NW Sec. 6 Twp. 35 Rge. 14 (E) (W) W

County Barber Total Depth 4865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: K & E Drilling, Inc.

Address: 719 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 3:30 PM Day 21st Month Oct. Year 1965

The Above well was plugged as follows:

 100' of 13 3/8" surface pipe, cement circulated. 816' of 8 5/8" surface
 pipe, cemented with 125 sacks. 200' of 8 5/8" surface pipe recovered from
 the hole. Hole was filled with drilling mud to 100', 1st cementing plug,
 bridged solid with hulls on fluid at 100', and cemented with 50 sacks.
 Hole was filled with to 40', 2nd cementing plug, bridged solid with hulls
 on fluid at 40', and cemented with 30 sacks to the base of the cellar.
 Rat and mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Archie Elving*
Well Plugging Supervisor

DATE 10/26/65
 INV. NO. 2032-W