

15-007-30052-0000

9P

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JUL 6 1965
7-6-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name Davis Ranch Well No. # 1-6

Location Approx. C S/2 NW Sec. 6 Twp. 35 Rge. 14 (E) (W) W

County Barber Total Depth 4875'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: K & E Drilling, Inc.

Address: 719 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 9:30AM Day 30th Month June Year 1965

The Above well was plugged as follows:

854' of 8 5/8" surface pipe, cement circulated with 400 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged
with hulls, and cemented with 25 sacks. Hole was filled with drilling
mud to 40', 2nd cementing plug, bridged solid with hulls, and cemented
with 10 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-7-65

INV. NO. 1416-W