



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1965
10-25-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 719 Union Center, Wichita, Kansas

Lease Name: Davis Ranch Well No. # 2-6

Location: C NE NW Sec. 6 Twp. 35 Rge. 14 (E) (W) W

County Barber Total Depth 4865' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

100' of 13 3/8" surface pipe, cement circulated. 816' of
8 5/8" surface pipe, cemented with 125 sacks. This 8 5/8" to
be recovered. Fill hole with drilling mud to 100', 1st cementing
plug, bridged with hulls, and cement with 50 sacks. Fill hole with
drilling mud to 40', 2nd cementing plug, bridge with hulls, and cem-
with 30 sacks to base of cellar. Bridge and cement rat hole with 2
sacks.

Very truly yours,

Archie Elving