

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,847.0000

LEASE NAME Lawrenz

WELL NUMBER 1-16

SPOT LOCATION C NE SW

SEC. 16 TWP. 30 RGE. 12 (Section) (W)

COUNTY Barber

Date Well Completed 7-18-84

10:00 PM

Plugging Commenced 7-18-84

11:30 PM

Plugging Completed 7-18-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4785'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. Heavy mud and 50 sacks at 1085'; heavy mud and 40 sacks at 620; heavy mud and 40 at 310' heavy mud with Howco, solid bridge and 10 sacks at 40'. 10 sacks in rathole; no sacks in mousehold and 5 sacks in water well. Used 60/40 Pozmix, 2% gel and 3% cc. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
7-31-84
JUL 31 1984

(Signature) [Signature]
STERLING DRILLING COMPANY
F. A. Wuellner, Secretary
(Address) P. O. Box 129, Sterling, Kansas 67579



SUBSCRIBED AND SWORN TO before me this 20 day of July, 1984
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

15-007-21847-0000

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- LAWRENZ #1-16

Located: C NE SW, Section 16-30S-12W, Barber County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 8, 1984

COMPLETED: July 18, 1984

TOTAL DEPTH: 4785'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 266 Surface Soil and Sand	Ran 6 joints 8 5/8" OD casing. 250.82' pipe set at 263' K.B.
266 - 1410 Shale	Cemented with 200 sacks Common, 2% gel and 3% cc. Plug down at 10:00 PM, 7-8-84, by Howco.
1410 - 1750 Shale and Lime Stringers	
1750 - 4785 Lime and Shale	Plugged.

Deviation Surveys: 1 1/2° at 2810'
1 3/4° at 4232'