


15-007-10230-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 16 Twp. 30S Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines C NE/4
Lease Owner Cameron K. Reed
Lease Name House Well No. 6
Office Address Box 13262, Kansas City, Missouri
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 3, 19 73
Application for plugging filed July 3, 19 73
Application for plugging approved July 3, 19 73
Plugging commenced July 3, 19 73
Plugging completed July 3, 19 73
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	413'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 250 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED

STATE CORPORATION COMMISSION

JUL 6 1973

7-6-73

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1973

My commission expires May 9, 1975 Betty Brandt Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Cameron K. Reed DRILLING COMMENCED: June 26, 1973
 Box 13262
 Kansas City, Missouri

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: July 3, 1973
 505 Union Center
 Wichita, Kansas 67202

CASING RECORD: 11 Jts. 413' - 8-5/8" LOCATION: House No. 6
 cemented with 350 sacks C NE/4
 Section 16-30S-12W
 Barber County, Kansas

0 - 85 Sand
 85 - 756 Red bed & shale
 756 - 1530 Shale & shells
 1530 - 1820 Shale
 1820 - 2125 Lime & shale
 2125 - 2225 Lime
 2225 - 2383 Shale
 2383 - 3130 Shale & lime
 3130 - 3260 Lime & shale
 3260 - 3350 Shale & lime
 3350 - 3660 Shale & lime
 3660 - 3710 Lime & shale
 3710 - 3860 Shale & lime
 3860 - 3880 Lime
 3880 Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 7-6-73
 JUL 6 1973
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves President

STATE OF KANSAS)
) ss:
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 5th of July, 1973.

Betty Brandt
 Betty Brandt Notary Public

My commission expires:
 May 9, 1975