

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form GP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32556
Name: Reh Oil and Gas, LLC
Address 1: 1501 E First
Address 2: _____
City: Pratt State: Ks Zip: 67124 + _____
Contact Person: Doug Reh
Phone: (620) 672-8111
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 025-21542-00-00
Spot Description: se,se,se,nw
se se se nw Sec. 2 Twp. 34 S. R. 21 East West
2,755 Feet from North / South Line of Section
2,693 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Clark
Lease Name: Harper Ranch Well #: JC8
Date Well Completed: 5-13-12
The plugging proposal was approved on: 5-10-12 (Date)
by: Daniel Bersconi (KCC District Agent's Name)
Plugging Commenced: 5-13-12
Plugging Completed: 5-13-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

First plug at 960' with 50sx cmt. Second plug at 400' with 50 sx cmt. Third plug at 60' with 20sx cmt. Rat hole plugged with 30sx cmt. Mouse hole plugged with 20 sx cmt. Plugged by Quality Cementing with 60/40 pozmix 4% gel.

Plugging Contractor License #: 5142 Name: Sterling Drilling Company
Address 1: 463 Yucca LN Address 2: _____
City: Pratt State: Kansas Zip: 67124 + _____
Phone: (620) 672-9508
Name of Party Responsible for Plugging Fees: Reh Oil and Gas LLC
State of Kansas County, Pratt, ss.
Douglas V Reh Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn or oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Douglas V Reh

LITHOLOGY STRIP LOG

WellSight Systems

Scale 1:240 (5"=100') Imperial
Measured Depth Log

Well Name: REH Oil and Gas Company
Location: SE SE SE NW
License Number: API: 15-025-21542-00-00
Spud Date: May 4, 2012
Surface Coordinates: 2755' FSL, 2693' FEL Section 2-Twp 34 South - Rge 21 West
Harper Ranch
Bottom Hole Vertical Hole
Coordinates:
Ground Elevation (ft): 1879 K.B. Elevation (ft): 1892
Logged Interval (ft): 4400 To: 5548 Total Depth (ft): 5548
Formation: Misslssippi
Type of Drilling Fluid: Chemical Mud, Displace at 3600'.
Region: Clark County, Kansas
Drilling Completed: May 12, 2012

Printed by MUD.LOG from WellSight Systems 1-800-447-1534 www.WellSight.com

OPERATOR

Company: REH Oil & Gas Company
Address: Doug Reh
1501 E 1ST ST
Pratt, Kansas 67124-2069

GEOLOGIST

Name: W. Scott Alberg
Company: Alberg Petroleum, LLC
Address: 609 Meadowlark Lane
Pratt, Kansas 67124

FORMATION TOPS

	SAMPLE TOPS	LOG TOPS
DOUGLAS SHALE	4473(-2578)	4477(-2582)
LANSING	4540(-2645)	4543(-2648)
STARK	4988(-3093)	4990(-3095)
MARMATON	5130(-3235)	5137(-3242)
PAWNEE	5220(-3325)	5224(-3329)
CHEROKEE GROUP	5278(-3383)	5283(-3388)
MORROW SHALE	5399(-3501)	5400(-3502)
MORROW SAND	5440(-3545)	5445(-3540)
MISSISSIPPIAN	5498(-3603)	5502(-3607)
RTD	5548(-3653)	
LTD		5554(-3659)