

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,900-0000

LEASE NAME Warren

WELL NUMBER 2-35

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from ⁿ Section Line

2310 Ft. from ^w Section Line

SEC. 35 TWP. 30S RGE. 12W (E) or (W) (W)

COUNTY Barber

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. St. N. #300 Wichita, Kansas 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed _____

Character of Well Oil

Plugging Commenced 6-12-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-15-00

The plugging proposal was approved on _____ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13-5/8"	287'	None
				7"	4765'	1600'

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 2001
CONSULTATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each. Set bridge plug @2820' with 2 sks. cement on top. Shot pipe @2200', 2000' and 1600', pulled pipe up to 700', pumped 75 sks. cement and 10 sks. gel, pulled to 300', pumped 75 sks. cement, pulled to 40' and circulated 40 sks. cement to surface. 60/40 pos. 6% gel
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 21st. day of June 2000

[Signature]
Notary Public

My Commission Expires: _____

IRENE HERZBERG
State of Kansas
My Appt. Exp. Aug. 24, 2001

Form CP
Revised 05-