

15-007-20340-00-01

Form CP-4
Rev. 12-15-80

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas. 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 32 TWP. 30 RGE. 12w E/W
Location as in quarters or footage from lines:
C SE

Locate Well
correctly on above
Section Platt.

Lease Owner Raymond Oil Co., Inc.
Lease Name Olsen #1-A Well No. _____
Office Address One Main Place, Suite 900, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 12/12/83
Plugging completed 12/15/83
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 3939'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	263'	none
				4 1/2"	3071'	2436'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped 35 sacks cement & plug to 2600'. Shot pipe at 2436' Pulled 62 joints.
Plugged well with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug & 125
sacks 60/40 poz 2% gle 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, 88.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of December 19 83

My Commission expires:



Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1983
12-21-83
CONSERVATION DIVISION
Wichita, Kansas

RAYMOND OIL COMPANY, INC.
 200 W. DOUGLAS
 WICHITA, KS 67202
 #1-A OLSON 'OWWO'
 CONTR STERLING DRILLING CTY BARBER
ROTARY DRILLERS' LOG

32-30-12W 32-30-12W
 C SE/4 C-SE

OPERATOR: Sidwell Oil & Gas Inc. 11/15/79 DRILLING COMMENCED: July 26, 1975
 P. O. Box 2475 TARK 297

LOG TOPS	DEPTH	LOG TOPS	DEPTH
COTTONWD	2513	NEVA	2563
RED EAG	2655	IND CF	2782
LANG	2878	TARK	2959
EMP	3016	HOW	3123
TOP	3191	HEEB	3703
TOR	3720	DOUG	3754
LANS	3902	Rtd	3930

NEW INFO: OPERATOR W. S. SIDWELL OIL & GAS INC. DRILLING COMPLETED August 3, 1975
 (1) 3732 - 45-45-45-45, REC 50' DM.
 (2) 3732-3780/30-30-30-30, REC 50'
 (3) 3817-3861/30-45-30-45, REC 50'
 GCM, SIP 725#/45"-1044#/45", FP 17-34#
 LOCATION: M. Olson No. 1250-1324#
 Section 32-30S-12W Barber County, Kansas

KANSAS
 INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

- 0 - 70 Sand
- 70 - 264 Redbed
- 264 - 570 Shale & shells
- 570 - 1200 Shale & shells
- 1200 - 1734 Shale
- 1734 - 1940 Lime
- 1940 - 2195 Lime shale & sand streaks
- 2195 - 2550 Shale & lime
- 2550 - 2838 Lime shale & sand streaks
- 2838 - 3090 Shale & lime
- 3090 - 3360 Lime & shale, sand streak & some chert
- 3360 - 3715 Shale & lime
- 3715 - 3780 Lime
- 3780 - 3861 Sand & shale
- 3861 - 3865 Lime
- 3865 - 3930 Sand shale & lime streaks

LOG TOPS: DEPTH:
 Cottonwd 2513
 Neva 2563
 Red Eag 2655
 Ind Cf 2782
 Lang 2878
 Tark 2959
 Emp 3016
 How 3123
 Top 3191
 Heeb 3703
 Tor 3720
 Doug Sd 3754
 Lans 3902
 Rtd 3930

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.
 By Phil Graves President

STATE OF KANSAS)
) SS:
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 7th day of August, 1975

My commission expires: May 9, 1979

Betty Brandt Notary Public
 RECEIVED
 STATE CORPORATION COMMISSION

NOV 9 1983
 11-9-83
 CONSERVATION DIVISION
 Wichita, Kansas

RAYMOND OIL COMPANY, INC. 15-007-20340-00-01 32-30-12W
 200 W. DOUGLASS ST. #1-A OLSON 'OWWO' C SE/4
 WICHITA, KS
 CONTR STEELING L. LANG c BARBER

GEOL _____ FIP # NURSE M.J.
 1832 KB M 2/26/75 CARD ISSUED 11/15/75 F 1,000 MCF/GPD
 TARK 2972-78

+	+
+	+
+	*

API 15-007-20,340-A

LOG	TOPS	DEPTH	DATUM
COTTONWOOD	2513	-681	
NEVA	2563	-731	
RED EAG	2655	-823	
IND CV	2782	-950	
LANG	2878	-1046	
TARK	2959	-1127	
EMP	3016	-1184	
HOW	3123	-1291	
TOP	3191	-1359	
HEEB	3703	-1871	
TOR	3720	-1888	
DOUG SD	3754	-1922	
LANS	3902	-2070	
RTP	3939	-2098	

OLD INFO: OPERATOR WAS SIBBELL OIL &
 GAS #1 OLSON; SPD 7/26/75 SET 8-5/8"
 263/30SX; COMPLETED AS D&A/LANS 8/3/75
 DST (1) 3732-3780/45-45-45-45, REC 50' DM,
 NS, SIP 720#/45"-1044#/45", FP 17-
 34#
 DST (2) 3732-3780/30-30-30-30, REC 90'
 GCM, 120' THIN M, 120 MW, SIP 1250-
 1324#, FP 55-156#
 DST (3) 3817-3861/30-45-30-45, REC 90'
 GCM, 60' GCMW, SIP 1287-1269#, FP
 37-83#

NEW INFO: 11/26/79, WSH DWN
 TO 3077; 11/26/79, WSH DWN
 TO 3077

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RAYMOND OIL COMPANY, INC. #1-A OLSON 'OWWO' 32-30-12W
 MICT T CO, PF 24/2972-78, AC 250 GAL MUD-ACID, FRAC 1, 2, 3, 4
 & NITROGEN, SWB DWN, KO FLO, SI

RECEIVED
 STATE CORPORATION COMMISSION

NOV 9 1983
 11-9-83
 CONSERVATION DIVISION
 Wichita, Kansas