

15-007-00101-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barber County, Sec. 33 Twp. 30 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Tomlinson-Kathol, Inc.

Lease Name Olson Well No. 1

Office Address 414 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1/2/ 19 62

Application for plugging filed 1/2/ 19 62

Application for plugging approved 1/2/ 19 62

Plugging commenced 1/2 19 62

Plugging completed 1/2/ 19 62

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water			8-5/8"	215'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with mud to a depth of 190 feet where a plug was set and cemented with 20 sacks of cement. Mud was again put into the hole to a depth of 40 feet. Where the second plug was set and cemented with 10 sacks of cement. Casing was cut off below ground level and the location abandoned.

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1962
1-10-62
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Tomlinson-Kathol, Inc.
Address 414 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Richard C. Davis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
414 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 19 62

My commission expires 1/19/65
Esther Lanane
Notary Public.

15-007-00101-0000

DRILLERS LOG
TOMLINSON-KATHOL, INC.
1 OLSON
C NE SW, SEC. 33-30S-12W
BARBER COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced: 12/21/61
Completed: 1/2/62
Elevation: 1734 KB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	40	Surface Clay	
40	215	Red Bed & Rock	
215	280	Rat Hole	216' 8-5/8" Surf. Csg. @/150 sack cement
280	614	Red Bed	
614	950	Red Bed & Shale	
950	1295	Shale	
1295	1455	Shale & Lime	
1455	1680	Lime & Shale	
1680	1720	Shale	
1720	1768	Anhydrite	
1768	1790	Shale & Lime	
1790	1870	Lime & Shale	
1870	1975	Lime	
1975	2705	Lime & Shale	
2705	2930	Shale & Lime	
2930	3120	Lime & Shale	
3120	3220	Shale & Lime	
3220	3400	Lime & Shale	
3400	3515	Shale & Lime	
3515	3650	Lime & Shale	
3650	3675	Lime & Sand	
3675	3695	Lime & Shale	
3695	3793	Lime & Shale	Heebner 3609
3793	3800	Shale & Lime	Douglas Shale 3639
3800		Rotary Total Depth	Douglas Sand 3662 Brown Lime 3792

RECEIVED
STATE CONSERVATION COMMISSION
JAN 10 1962
1-10-62
CONSERVATION DIVISION
Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

State of Kansas)
) SS:
County of Sedgwick)

Richard C. Davis
Richard C. Davis, Geologist

Subscribed and sworn to before me this 9th day of January, 1962.

Esther Lamone
Esther Lamone, Notary Public

My Commission Expires: 1/19/65