

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Lyon County, Sec. 21 Twp. 20 Rge. 10 E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
NW SW


Lease Owner Joe Wendling etal  
Lease Name Wendling Well No. 1  
Office Address Olpe, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole

Date Well completed 10/16/77 19  
Application for plugging filed 10/16/77 19  
Application for plugging approved 10/16/77 19  
Plugging commenced 10/16/77 19  
Plugging completed 10/16/77 19  
Reason for abandonment of well or producing formation

No producing formation found  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Hickey  
Producing formation Depth to top Bottom Total Depth of Well 2350  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Water sand & shale	salt water	1275	1408	8 5/8"	80'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with rotary mud from TD to 200' and set bridge plug and cemented with 12 sacks cement. Filled with mud to 40' and set bridge plug and cemented with 8 sacks cement. Plugged rat hole and cemented with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 05 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jackman & Jackman

STATE OF Kansas COUNTY OF Greenwood, ss.  
C. R. McClelland (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C R McClelland  
(Address)

SUBSCRIBED AND SWORN TO before me this 1 day of November, 19 77

Robert H. Day  
Notary Public.

My commission expires August 29, 1979



WELL LOG

Company Joe Wendling etal  
 Farm Wendling  
 Well 1  
 Location NW SW of 21 20 10E Lyon County, Kansas  
 Commenced 10/11/77  
 Completed 10/16/77  
 Casing 80' of 8 5/8" cemented with 45 sacks  
 Contractor Jackman & Jackman  
 Production D & A  
 Total Depth 2350'

Soil & clay	0 -	6
Shale & shells	6	81
Lime & shale	81	410
Shale & shells	410	865
Lime & shale	865	1136
Shale & shells	1136	1273
Lime	1273	1275
Water sand & shale	1275	1408
Lime	1408	1499
Shale	1499	1521
Lime	1521	1836
Shale & shells	1836	1985
Shale & lime	1985	2170
Shale & shells	2170	2244
Sand	2244	2250
Sandy shale	2250	2256
Shale & shells	2256	2350

0' is 4' above ground level.

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 03 1977

CONSERVATION DIVISION  
 Wichita, Kansas