


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

County. Sec. 33 Twp. 30S Rge. 12W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
1830' FSL & 660' FEL  
Lease Owner Texas Oil & Gas Corp.  
Lease Name Olson "A" Well No. 1  
Office Address 200 W. Douglas-Suite 300, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above  
Section Flat

Dry Hole  
Date Well completed December 31, 1979  
Application for plugging filed Verbal Application 1979  
Application for plugging approved Verbal Approval 1979  
Plugging commenced December 31, 1979  
Plugging completed December 31, 1979  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 1979

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,825'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	290'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 3,825 ft. (rotary total depth) to 290 ft. Set plug at 290 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 290 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 20 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, Kansas


STATE RECEIVED  
JAN 8 1980  
CONSERVATION COMMISSION  
WICHITA, KANSAS

STATE OF Kansas COUNTY OF Sedgwick  
Dean Britting, Agent (Signature of owner) \_\_\_\_\_

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address).

SUBSCRIBED AND SWORN TO before me this 7th day of January, 1980



Elsie Willison  
Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 33 T. 30S R. 12W  
LOC. 1830' PSL & 660' FEL

FARM Olson "A" NO. 1

COUNTY Barber

ROTARY TOTAL DEPTH 3,825'  
COMM. December 19, 1979 COMP. December 31, 1979  
CONTRACTOR H-30, Inc. (Rig #5)  
ISSUED January 7, 1980

CASING

10 3/4" Set at 290' cemented w/300 sxs cement  
8 5/8"  
5 1/2"  
4 1/2"

ELEVATION 1,699' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Shale	1,006'
Shale and Lime	1,950'
Lime and Shale	2,170'
Shale and Lime	2,347'
Lime and Shale	2,790'
Shale and Lime	2,864'
Lime and Shale	2,906'
Shale and Lime	3,279'
Lime and Shale	3,480'
Shale and Lime	3,825'
Rotary Total Depth	3,825'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
Dean Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 7th day of January, 1980.



*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982

RECEIVED  
STATE CORPORATION COMMISSION  
JAN - 8 1980  
1-8-80  
CONSERVATION DIVISION  
Wichita, Kansas