

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22190-00-01
Spot: SWSW Sec/Twnshp/Rge: 12-30S-12W
660 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: HOUSE Well Number: 1
County: BARBER Total Vertical Depth: 2848 feet

Operator License No.: 30265
Op Name: OSPREY OIL & GAS, INC.
Address: PO BOX 3398
ENGLEWOOD, CO 80155

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 252 WITH 195 SX CMT
Production: Size 4.5 feet: 2844 WITH 125 SX CMT
Liner: Size feet: 92.56

Well Type: EOR UIC Docket No: E25767.1 Date/Time to Plug: 07/10/2001 9:30 AM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (316) 886-5665

Proposed Plugging Method: SAND TO 2600' & 4 SX CMT. 1ST PLUG AT 700' WITH 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/10/2001 10:30 AM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2826'. PERFS AT 2645-49.5'. SANDED BACK TO 2590' AND PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. RUN 2 3/8" TUBING IN TO SPOT PLUGS THROUGH. LOAD HOLE WITH GEL. 1ST PLUG AT 700' WITH 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED

DATE 7-23-01

INV. NO. 2002060099

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

RECEIVED
KANSAS CORPORATION COMMISSION

Signed

Stephen J. Pfeifer
(TECHNICIAN)

JUL 20 2001
7-20-01

CONSERVATION DIVISION

JUL 13 2001

Form CP-2/3