

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01023-00-02
Spot: SWSWSE Sec/Twnshp/Rge: 12-30S-12W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: HULL OWWO Well Number: 1-A
County: BARBER Total Vertical Depth: 2899 feet

Operator License No.: 30265
Op Name: OSPREY OIL & GAS, INC.
Address: PO BOX 3398
ENGLEWOOD, CO 80155

Conductor Pipe: Size feet:
Surface Casing: Size 10 feet: 968
Production: Size 5.5 feet: 2836 WITH 200 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 07/05/2001 4:30 PM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (316) 886-5665

Proposed
Plugging
Method:

CIBP @ 2490' & 2 SX CMT ON TOP. 1ST PLUG AT 1000' WITH 10 SX GEL & 75 SX CMT. 2ND PLUG AT 400'
WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER
Date/Time Plugging Completed: 07/05/2001 5:45 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2770'. PERFS AT 2648-52 & 2556-60'. CIBP @ 2770' & 2575'. SET CIBP @ 2490' & PUT 2 SX CMT ON TOP OF CIBP
THROUGH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 1000' WITH 10 SX GEL & 75 SX CMT.
2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 01 2001
8-1-01

CONSERVATION DIVISION

INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1850' OF 5 1/2" CASING.

Plugged through: TBG

DATE 7-11-01
INV. NO. 2002060036

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

JUL 09 2001

Form CP-2/3

NP