

1 040354

11-16

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,231-0000
SE NE, SEC. 3, T 35 S, R 15 W/R
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9026
Operator: Clark Exploration
Name & Address Box 245
Hardtner, KS 67057

Lease Name Z-Bar Well # 1-3
County Barber 163.09
Well Total Depth 5018 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 568

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 11 Year: 19 89

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5012' PBDT 5012' Perfs at 4905-22'
1st plug sand back to 4855' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 16 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4855' and dumped 4 sx cement on top of
sand bridge with bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 600 psi and shut in 300 psi.

NOV 27 1989
11-27-89

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 4200' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89
INV. NO. 26626

Signed Stephen J. Pfeifer
(TECHNICIAN)