

1041360  
TO: STATE CORPORATION COMMISSION

7-19

API NUMBER 15-007-22,123-00-01  
40' W C E/2 E/2 SEC. 21, T 30 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 2640 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 700 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME KUMBERG WELL # 4

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER

OPERATOR LICENSE # 31881 WELL TOTAL DEPTH 4675 151.94 FEET

OPERATOR: MCGINNESS OIL COMPANY PRODUCTION CSG: SIZE 4 1/2" @ 4666' WITH NA SX

NAME AND ADDRESS 150 N MAIN, SUITE 1026 SURFACE CASING: SIZE 8 5/8" @ 332' WITH SX

WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-27,341 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104 PHONE NUMBER 316-886-5665

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE LICENSE NUMBER 31528

ADDRESS PO BOX 467 CHASE, KS 67524 PHONE NUMBER 316-938-2943

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 25 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DOUGLAS MCGINNESS, SR.

(COMPANY NAME) MCGINNESS OIL COMPANY (PHONE)

WERE: PERFS AT 4562-4568

SAND BACK TO 4500' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 19 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED BACK TO 4500' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS. MAXIMUM PSI = 500#. PUMPED HOLE IN SURFACE PIPE-PUMPED 10 BELS OVER CAPACITY OF 8 5/8" SURFACE PIPE

WAIT ON RIG. SEE ATTACHED PAGE.

STATE CORPORATION COMMISSION  
7-22-99  
JUL 22 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES LLC. RECOVERED 2000' OF 4 1/2" CASING. IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

I (DID) OBSERVE THIS PLUGGING.

DATE 7-26-99

SIGNED Stephen C. Pfeifer (TECHNICIAN) FORM CP-2/3

INV. NO. 60073

(2)

Kumberg #4 continued

7-8-99

Mike's Testing & Salvage rigged up on well and ran tubing into 120' staked out. (Had notched collar on bottom of tubing. Rotated tubing made approximately 4' of hole. Got solid. Pulled out of hole with tubing.

7-17-99

Clarke Corporation moved on and drilled cement out of surface pipe from 120' to 345'.

7-19-99

Loaded hole with gel- spot plugs inside

7<sup>7</sup>/<sub>8</sub>" hole and 8<sup>5</sup>/<sub>8</sub>" surface pipe through 2<sup>3</sup>/<sub>8</sub>" tubing.

1st plug at 700' with 50 sx cement.

2nd plug at 345' with 50 sx cement.

3rd plug at 40' with 10 sx cement.

Allied completed the cementing using 60/40 pozmix 6% gel.

Completion time at 11:30a.m.

RECEIVED  
STATE CONSERVATION COMMISSION

JUL 22 1999  
7-22-99  
CONSERVATION DIVISION  
Wichita, Kansas