

1080173

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,872-0000

C NE NE, SEC. 21, T 30 S, R12  
4620 FSL feet from NXX section line  
660 FEL feet from WXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Lawrenz Well # 1-21

Operator: Texas Energies, Inc.  
Name & Address: P. O. Box 947  
Pratt, KS 67124

County Barber  
Well Total Depth 4700 152.75 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 305 300

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 1:00 pm Day: 19 Month: July Year: 1984

Plugging proposal received from Roger Baker

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1000' with 50 sx cement

2nd plug at 360' with 50 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement:  
Plugging Proposal Received by J. H. [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:15 pm Day: 19 Month: July Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1000' with 50 sx cement, 2nd plug at 360' with 50 sx cement, 3rd plug - pumped 10 sx cement from 40' to surface

No solid bridge since cellar was full of mud

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 7-31-84

Signed J. H. [Signature] (TECHNICIAN)

INV. NO. 2221

7-19 AUG 22 1984

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 24 1984  
7-24-84  
CONSERVATION DIVISION  
Wichita, Kansas