

1041355

TO: STATE CORPORATION COMMISSION

6-25

API NUMBER 15-007-20,543-00-01
SW SE SE SEC. 21, T 30 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KUMBERG WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 153.57

OPERATOR LICENSE # 31881

WELL TOTAL DEPTH 4725 FEET

OPERATOR: MCGINNESS OIL COMPANY OF KS PRODUCTION CSG: SIZE 4 1/2" @ 4695' WITH 300 SX

NAME AND 150 N MAIN, SUITE 1026 SURFACE CASING: SIZE 8 5/8" @ 329' WITH 225 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 3:30 PM DAY: 25 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: BP @ 3550'. PERFS AT 3488-90 & 3458-62

PUMP DOWN 4 1/2" CASING WITH 200# HULLS AND 25 SX COMMON CEMENT. STOP PLUG AT 2160' (LOCKED

UP). PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" WIPER PLUG & 100 SX CEMENT. MAXIMUM PRESSURE AT 500#. SHUT IN WITH 400#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 25 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT

PUMPED DOWN 4 1/2" CASING WITH 200# HULLS AND 25 SX OF COMMON CEMENT. STOP PLUG AT 2160'

(LOCKED UP). PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL

100# HULLS - 8 5/8" WIPER PLUG & 100 SX CEMENT. MAXIMUM PRESSURE AT 500#. SHUT IN WITH

400#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES, LLC. RECOVERED 2000' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

DATE 7-9-99

INV. NO. 60019

STATE OF KANSAS
WICHITA, KANSAS
JUL 21 1999
RECEIVED
PLUGGING SECTION

INVOICED

[Signature]