

15-159-30260-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name O.A. Sutton

Complete Address: 407 Insurance Bldg. Wichita, Kansas

Lease Name Goodfellow Well No. # 2

Location C NW SE Sec. 28 Twp. 19 Rge. 8 (W)

County Rice Total Depth 3391'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Ralph Comstock Pipe Pulling

Address: Staford, Kansas License No. # 490

Operation Completed: Hour 6 PM Day 24 Month 6 Year 66

The Above well was plugged as follows:

8 5/8"-200'-Circulated w/cement. 5 1/2"-3391'-Cemented. Plug back to 3368'.

Top Perforations-3350'. Sand hole to 3325'. 5' Sax. cement 3325' to 3285'.

Mud 3285' to 190'. Bridge 190' to 180'. Cement 180' to 0.

Pulled 2430' - 5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6/27/66
INV. NO. 3490-W