

2 070187

8-16

API NUMBER 15- 159-19271-0000

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW, SEC. 28, T 19 S, R 8 W&amp;E

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5822

Lease Name Hill Well # 25-3

Operator: Gressel Corporation

County Rice 110.60

Name &amp; Address Box 322

Well Total Depth 3403 feet

Haysville, KS 67060

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 202

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Gressel Corporation License Number 5822

Address

Company to plug at: Hour: 12:00 Day: 16 Month: 8 Year: 19 89

Plugging proposal received from Dewey Gressel

(company name) (phone)

were: Sand bottom to 3280' & 6 sx - 75' plug at 1150' - 75' plug at 750' -  
260' to surface.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1989

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 4:00 Day: 16 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 3280' &amp; 6 sx of common - shot 5-1/2"

casing off at 1454' - pulled to 1150' &amp; pumped 75' plug - pulled to 750' &amp;

pumped 75' plug - pulled to 380' &amp; pumped 4 hulls - pulled to 260' &amp; pumped

to surface - used 185 cu ft of slurry.

Remarks: Allied #7119

INVOICED (Additional description is necessary, use BACK of this form.)

I (did / xxxxxxxx) observe this plugging.

DATE 8-30-89

INV. NO. 25758

8-16

Signed

(TECHNICIAN)

FORM CP-2/3  
Rev. 01-84