

2070177

8-7 15-159-19275-0000

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

E-13,839

NW, SEC. 21, T 19 S, R 8 W/EX

feet from N/S section line

feet from W/E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5822

Lease Name McKinnis Well # 11-1

Operator: Gressel Corporation

County Rice 110.34

Name &amp; Address Box 322

Well Total Depth 3395 feet

Haysville, KS 67060

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 202

Abandoned Oil Well Gas Well Input Well X SWD Well D&amp;A

Other well as hereinafter indicated

Plugging Contractor Gressel Corporation License Number 5822

Address

Company to plug at: Hour: 11:00 Day: 7 Month: 8 Year: 19 89

Plugging proposal received from Dewey Gressel

(company name) (phone)

were: Sand bottom to 3246' & 6 sx - 75' plug at 1150' - 75' plug at 750' -  
260' to 0

RECEIVED  
STATE CORPORATION COMMISSION  
08-18-89  
AUG 18 1989

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Jack Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:00 Day: 7 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 3246' and 6 sx of common - shut 5-1/2" off  
at 2786' - pulled to 1150' and pumped 75' plug - pulled to 750' and pumped 75'  
plug - pulled to 260' and pumped to surface - used 182 cu ft of slurry.

Remarks: Allied #1190 Cement fell to 110' - filled to surface 60/40 4%  
Additional description is necessary, use BACK of this form.)

INVOICED

I (did XXXXXXXX) observe this plugging.

DATE 8-21-89

INV. NO. 25691

Signed

(TECHNICIAN)

FORM CP-2/3  
Rev. 01-84