

2 070179

API NUMBER 15-

E-13,839

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE, SEC. 17, T 19 S, R 8 W&E

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5822

Lease Name Kolberg Well # 4-1 (INJ)

Operator: Gressel Corporation

County Rice 113.10

Name & Address Box 322

Well Total Depth 3480 feet

Haysville, KS 67060

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 203

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Gressel Corporation License Number

Address

Company to plug at: Hour: 4:00 Day: 9 Month: 8 Year: 19 89

Plugging proposal received from Dewey Gressel

(company name) (phone)

were: Sand bottom to 3240' & 5 sx - 75' plug at 1150' - 75' plug at
750' - 250' to surface

RECEIVED
STATE CORPORATION COMMISSION

JUG 18 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:45 Day: 9 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 3240' & 5 sx of common - shot off 4-1/2"

at 2625' - pulled to 1150' & pumped 75' plug - pulled to 750' and pumped

75' plug - pulled to 260' and pumped to surface

Used 190 cu. ft. of slurry.

Remarks: Allied #1191 Cement fell 140' - Allied brought to surface w/slurry.

INVOICED

If additional description is necessary, use BACK of this form.)

(did XXXXXX observe this plugging.)

DATE 8-21-89

INV. NO. 25688

8-9

Signed

Jack Luthi
(TECHNICIAN)