

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20891-00-00
Spot: N2N2N2 Sec/Twnshp/Rge: 33-32S-37W
3963 feet from S Section Line, 2609 feet from E Section Line
Lease Name: STEBLETON Well #: 1-33
County: STEVENS Total Vertical Depth: 6250 feet

Operator License No.: 32390
Op Name: HIGH PLAINS PRODUCTION, LLC
Address: 3000 RESEARCH FOREST DR., STE 240
SPRING, TX 77381

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5950		WITH 2 SX CMT
PROD	5.5	6250	0	WITH 336 SX CMT
SURF	8.625	1766		WITH 780 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/10/2014 10:00 AM
Plug Co. License No.: 35060 Plug Co. Name: HOLMAN WELL SERVICE, LLC
Proposal Rcvd. from: FREDDY RAY Company: HOLMAN WELL SERVICE, LLC Phone: (806) 665-2550

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. PERFORATE @ 1796/ & CIRCUALTE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2014 6:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5950' WITH 2 SX CMT. PERFORATED @ 1796' & SET A CMT RETAINER AT 1740'. RAN TBG & CIRCULATED CMT WITH 450 SX CMT. PULLED TBG & TOPPED OFF WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6002	6018		MORROW

KCC WICHITA
APR 15 2014

Remarks: USED 60/40 POZMIX 4% GEL BY HOLMAN WELL SERVICES.

RECEIVED

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
APR 11 2014
KCC DODGE CITY