

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21628-00-01  
Spot: NESWNWSW Sec/Twnshp/Rge: 25-33S-31W  
1838 feet from S Section Line, 4905 feet from E Section Line  
Lease Name: SIMONSON Well #: 25-1  
County: SEWARD Total Vertical Depth: 7300 feet

Operator License No.: 34745  
Op Name: GLOBE ENERGY SERVICES LLC  
Address: 1015 N. COLLEGE AVE. PO BOX 255  
SNYDER, TX 79550

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1850		
PROD	5.5	7299	0	WITH 370 SX CMT
SURF	9.625	1754		WITH 545 SX CMT

Well Type: SWD UIC Docket No: D27929.0 Date/Time to Plug: 03/31/2014 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: RUFUS WILKS Company: GLOBE ENERGY SERVICES Phone: (325) 207-7799

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2014 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CMT PLUG IN 2 7/8" @ 6206' TO 6102'. (TAGGED WITH ELECTRIC LIINE) FOUND PACKER SET @ 2527'. FOUND TOP OF 2 7/8" TBG FISH @ 2727'. FOUND INSIDE OF 2 7/8" TBG PLUGGED. DRILLED OUT 2 7/8" TBG TO 6317'. COULD NOT MAKE ANY MORE HOLE. WASHED OVER 2 7/8" FISH TO 3341'. STILL STUCK AT 3352'. CASING LEAKS FROM 3130' TO 3360'. PERFORATE 8 HOLES IN 2 7/8" AT 6062'. COULD NOT PUMP INTO AT 1000#. PERFORATE 8 HOLES AT 5000'. COULD NOT PUMP INTO. REPERF @ 5000' IN ATTEMPT TO PENETRATE THE 2 7/8" TBG & THE 5 1/2" CASING. COULD NOT PUMP INTO AT 1000#. DUMP BAIL 104' OF CMT FROM 6206' TO 6102'. WAIT 24 HOURS & TAG AT 6102'. SET CIBP @ 1850' OVER CASING LEAKS. PERFORATE 4 HOLES AT 1808'. RUN TBG & PACKER TO 1350'. SPOT 75 SX CMT WITH 50# HULLS IN LAST 35 SX CMT, LEAVING 40 SX CMT OUT PERFS & 35 SX CMT INSIDE CASING. FULL RETURNS. PERFORATE 4 HOLES AT 550'. CIRCULATE CMT TO SURFACE WITH 150 SX CMT, LEAVING 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

APR 09 2014

RECEIVED

District: 01

Signed

*Ken Jehlik*  
(TECHNICIAN)  
*cc to WCC 4/09/14*

RECEIVED

APR - 3 2014

KCC DODGE CITY

*AW*