

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-00513-00-00  
Spot: SWNENESW Sec/Twnshp/Rge: 21-25S-31W  
2210 feet from S Section Line, 2999 feet from E Section Line  
Lease Name: BEACH Well #: 6  
County: FINNEY Total Vertical Depth: 2645 feet

Operator License No.: 32864  
Op Name: XTO ENERGY INC.  
Address: 210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2516		WITH 10 SX CMT
PROD	5.5	2598	0	WITH 150 SX CMT
SURF	8.625	538		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/27/2014 10:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: ALAN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Set CIBP @ 2516', circ hole w/ mud and cap CIBP w/ 10 sx cement. Mix & spot 50 sx to cover Anhydrite formation @ +/- 2000'. Perf squeeze holes @ 1100'. Set pkr @ 850' & squeeze BTW (800') w/ 75 sx cement. Test csg to 500 psi. Perf squeeze holes @ 550', mix & pump 170 sx cement & circ cement to surface. Cut off wellhead, weld on ID plate & restore location.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/28/2014 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2516' WITH 10 SX CMT. PLUG AT 2000' WITH 50 SX CMT. FULL CIRCULATION. PERFORATE @ 1100'. TIH W/TBG & PACKER TO 750'. ESTABLISH INJECTION RATE 2 BPM @ 400#. PUMP 75 SX CMT WITH 100# HULLS IN LAST 35 SX CMT AT 500#, LEAVING 40 SX CMT OUT PERFS & 35 SX CMT INSIDE CASING. PERFORATE @ 550'. ESTABLISH INJECTION RATE OF 2 BPM AT 400#. BLOW ON ANNULUS. PUMP 170 SX CMT VIA 5 1/2" CASING (120 SX OUTSIDE PERFS). NO CIRCULATION TO SURFACE. PUMP 35 SX CMT DOWN THE ANNULUS TO 400#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2621	2645		
2588	2606		
2566	2584		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

KCC WICHITA

APR 09 2014

RECEIVED

District: 01

Signed

*Ken Jehlik*  
4/10/14

(TECHNICIAN)

RECEIVED

APR - 3 2014

KCC DODGE CITY