

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22927-00-00
Spot: NENWSWSE Sec/Twnshp/Rge: 13-14S-24W
1200 feet from S Section Line, 2150 feet from E Section Line
Lease Name: SHELTON TRUST Well #: 1-13
County: TREGO Total Vertical Depth: 4480 feet

Operator License No.: 31160
Op Name: PHILLIPS EXPLORATION COMPANY L.
Address: 211 CEDAR RIDGE CT PO BOX 850
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/26/2014 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2379

Proposed Plugging Method: Ordered 220sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 03/26/2014 12:00 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st plug @1780 w/25 sx
2nd plug @790 w/100 sx
3rd plug @270 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY/RS

Plugged through: DP

KCC WICHITA

APR 07 2014

RECEIVED

District: 04

Signed Ed Schumacher
4/08/14 (TECHNICIAN)

CM

MAR. 28 2014