

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01131-00-00
Spot: SENWNW Sec/Twnshp/Rge: 9-30S-8W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: EVANS C Well #: 3
County: KINGMAN Total Vertical Depth: 4325 feet

Operator License No.: 34357
Op Name: ATLAS OPERATING LLC
Address: 15603 KUYKENDAHL, STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4322		100 SX
SURF	8.625	245		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/08/2013 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: LARRY PRIEST Company: ATLAS OPERATING Phone: (620) 532-9461

Proposed Plugging Method: 1) sand back to 4110 and place 10 sks cmt on top 2) Displace hole with 9.0 # mud. 3) 35 sks cmt plug @ 13004) 35 sks cmt plug at 850' 5) Circulate 115 sks cmt plug from 300 to surface

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/10/2013 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

10/18/13 MOVE IN RIG UP QUALITY WELL SERVICE UNIT. 10/09/13 PUMP 35 SXS. 200# HULLS DOWN TUBING. TAG TOP OF CEMENT AT 4010'. RIP CASING FREE AT 2025'. 10/10/13 PULL 5 1/2" CASING OUT OF HOLE LAYING DOWN. RUN IN HOLE WITH TUBING TO 1250'. PUMP 35 SKS CEMENT PLUG AT 1250'. PULL TUBING UPTO 800 AND PUMP 35 SXS. CEMENT PLUG AT 800'. PUMP 135 SKS CEMENT PLUG FROM 300' TO SURFACE. RIG DOWN QUALITY UNIT AND MOVE OFF.

Perfs:

Top	Bot	Thru	Comments
4197	4217		
4163	4174		


KCC WICHITA

Remarks:

APR 10 2014
RECEIVED

Plugged through: TBG

District: 02

Signed 
4/16/14 (TECHNICIAN)