

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21753-00-00
Spot: SENE Sec/Twnshp/Rge: 4-21S-18W
2100 feet from N Section Line, 555 feet from E Section Line
Lease Name: DIRKS 4A Well #: 1
County: PAWNEE Total Vertical Depth: 4560 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1212		WITH 550 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/29/2014 9:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: BILL SANDERS Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 4052' WITH 50 SX CMT. 2ND PLUG AT 1240' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS WitnessType: NONE
Date/Time Plugging Completed: 03/29/2014 11:00 AM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

Perfs:

1ST PLUG AT 4052' WITH 50 SX CMT. 2ND PLUG AT 1240' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

KCC WICHITA

APR 09 2014

RECEIVED

District: 01

Signed

Daniel Sellers
4/13/14
(TECHNICIAN)

RECEIVED

APR - 4 2014

KCC DODGE CITY

RAM