

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04330-00-00  
Spot: SESESE Sec/Twnshp/Rge: 1-18S-14W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: H.J. RIEDEL Well #: 1  
County: BARTON Total Vertical Depth: 3342 feet

Operator License No.: 31174  
Op Name: BIG HORN OIL CO., INC.  
Address: PO BOX 263  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	3326		250 SX
SURF	8.625	792		500 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2014 9:00 AM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.  
Proposal Rcvd. from: BRAD SWARLEY/RICK POP Company: BIG HORN DRILLING CO. Phone: (620) 793-3160

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 16 sx gel and 800 # hulls.  
PBTD - 3192'  
Perforations: 3137' - 3146', 3155' - 3160', 3168' - 3170', 3176' - 3192' and 3326' - 3342'.  
04/03/2014- Ordered 350 sx 60/40 pozmix 4% gel cement, 5 sx CC and 1000 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/03/2014 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1500' and 775'. Chase ran in hole with tubing to 3100'. Quality rigged to tubing and pumped 16 sx gel followed by 75 sx cement w/200 # hulls mixed in. No circulation of cement. Pulled tubing to 1500'. Quality rigged to tubing and pumped 200 sx cement w/500 # hulls mixed in. No circulation of cement. Pulled tubing to 800' and pumped 175 sx cement w/200 # hulls. No circulation of cement. Shut down overnight.  
04/03/2014- Ran in hole with tubing and tagged cement at 1875'. Pumped 50 sx cement w/200 # hulls and 50 sx cement w/3% CC. Left set 1 1/2 hours. Ran in hole to 800' and pumped 70 sx cement w/200 # hulls to circulate cement up 6" casing and 8 5/8" casing. Pulled tubing. Rigged to 6" casing with a swedge and pumped 20 sx cement. Circulated cement out 8 5/8" casing. Shut in and pulled off swedge. Hole standing full on 6" casing.

GPS: 38.50799 -098.81289

Perfs:

Top	Bot	Thru	Comments
3326	3342		
3176	3192		
3168	3170		
3155	3160		
3137	3146		

Remarks: QUALITY CEMENTING CO TICKET # 498

Plugged through: TBG


KCC WICHITA

APR 07 2014

RECEIVED

District: 04

Signed

  
(TECHNICIAN)  
4/08/14

CM

APR 03 2014