

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02079-00-00
Spot: NESWSE Sec/Twnshp/Rge: 11-10S-20W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: CROFFOOT B Well #: 10
County: ROOKS Total Vertical Depth: 3784 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3779		100 SX
SURF	8.625	259		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/01/2014 8:30 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed No Alt II records. Need to perf: 2350', 1680' and 1000'.
Plugging Open hole completion 3779' - 3784'.
Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/01/2014 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 2350', 1680' and 1000'.
Ran tubing to 3690'. Allied pumped 185 sx cement w/300 # hulls. Pulled tubing to 1845'.
Allied pumped 150 sx cement w/200 # hulls. Cement circulated. PTOH. Topped 5 1/2" casing
off w/15 sx cement. Hole standing full. Hooked up to backside and pumped 10 sx cement.
Maximum pressure 300 psi. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3779	3784		

Remarks: ALLIED

Plugged through: TBG

KCC WICHITA

APR 07 2014

RECEIVED

District: 04

Signed Richard Williams
(TECHNICIAN)

4/17/14

CM

APR 03 2014