

** OK TO INV. AS PLUG DT'S. W/IN 5 YR. BILLING*

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01805-00-00
Spot: N2NENE Sec/Twnshp/Rge: 7-30S-7W *CUTOFF.*
4950 feet from S Section Line, 660 feet from E Section Line
Lease Name: KOHMAN Well #: 3
County: KINGMAN Total Vertical Depth: 4536 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 12826 SW 77 AVE
ZENDA, KS 67159

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4300		190 SX
SURF	8.625	262		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2010 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DOUGLAS BRAMWELL Company: BRAMWELL PETROLEUM Phone: (620) 532-6019

Proposed Plugging Method: ACCORDING TO KCC REQUIREMENTS.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 07/09/2010 12:00 AM KCC Agent: STEVE VANGIESON


Actual Plugging Report:
SAND AT 4150'. BAILED 4 SXS CEMENT, PULLED SLIPS, HAD 6" STRETCH. LOG-TECH SHOT HOLES AT 1200'. RAN TUBING TO 1200' AND PUMPED 50 SXS 1% CC AND 100# HULLS. PULLED TUBING AND SHOT HOLES AT 750'. RAN TBG TO 750' PUMPED 50 SXS 1% CC AND 100# HULLS. PULLED TUBING AND SHOT HOLES AT 300'. PUMPED 120 SXS CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4206	4212		MISSISSIPPI
4168	4171		MISSISSIPPI
4153	4159		MISSISSIPPI
4146	4150		MISSISSIPPI

Remarks:
Plugged through: TBG

KCC WICHITA
APR 10 2014
RECEIVED

District: 02 Signed:  (TECHNICIAN)
4/10/14