

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00732-00-00
Spot: NWSWNWNW Sec/Twnshp/Rge: 2-11S-21W
4375 feet from S Section Line, 5007 feet from E Section Line
Lease Name: COOK Well #: 8
County: TREGO Total Vertical Depth: 3655 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3652		100 SX
SURF	8.625	190		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2014 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: CHRIS SCHOENHOFER Company: CHARTER ENERGY INC. Phone: (620) 282-8408

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 9 sx gel and 600 # hulls.
Production perforations: 3125' - 3568'
CIBP at 3600'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2014 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3600'. Tagged CIBP, pulled up and pumped 9 sx gel followed by 100 sx cement w/250 # hulls. Pulled tubing to 1672' and pumped 160 sx cement w/200 # hulls. Pulled all tubing. Topped off 5 1/2" casing w/65 sx cement.
8 5/8" x 5 1/2" annulus visually checked cement to surface.

GPS: 39.12884N -099.62775W

Perfs:

Top	Bot	Thru	Comments
3125	3568		

Remarks: QUALITY OILWELL TICKET # 008

Plugged through: TBG

KCC WICHITA

APR 07 2014

RECEIVED

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

APR 02 2014

Form CP-2/3