

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-21589-00-01

Spot: SWSWSENW

Sec/Twnshp/Rge: 8-24S-12E

2940 feet from S Section Line, 3660 feet from E Section Line

Lease Name: WILSON

Well #: 14

County: GREENWOOD

Total Vertical Depth: 1720 feet

Operator License No.: 5193

Op Name: BARNARD, R.L. DBA BARNARD OIL O

Address: 907 S 3RD PO BOX 535
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		1690		
PROD	4.5	1716		35 SX
SURF	8.625	82		40 SX
T1	2.375	1690		

Well Type: EOR

UIC Docket No: E10954.2

Date/Time to Plug: 03/26/2014 2:00 PM

Plug Co. License No.: 7719

Plug Co. Name: CHEEVER WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD L. BARNARD

Company:

Phone: (620) 437-2131

Proposed Plugging Method: As per KCC regulations

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/31/2014 9:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1700' pumped 10 sxs cement, pulled tubing to 844' pumped 10 sxs cement, pulled tubing to 241' pumped 55 sxs cement to surface, cement fell back to 100' let cement set up returned on Monday topped well off w/20 sxs cement, gel spacers between cement plugs, well perfed @ 840' 241'

RECEIVED

APR 07 2014

KCC Chanute Dist. #3

MH

KCC WICHITA

APR 10 2014

RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed

Michael D. Hoff
4/16/14

(TECHNICIAN)

cc to MK 4/16/14