

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21265-00-00  
Spot: NESWNWNW Sec/Twnshp/Rge: 21-17S-24W  
665 feet from N Section Line, 609 feet from W Section Line  
Lease Name: HABIGER - C Well #: 1  
County: NESS Total Vertical Depth: 4368 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| PROD   | 5.5   | 4354       | 0           | WITH 275 SX CMT |
| SURF   | 8.625 | 295        |             | WITH 175 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2014 9:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: MOE SMTIH Company: TRANS PACIFIC Phone: (316) 262-3596

Proposed Plugging Method: RTIH TO 1500' & CIRCULATED CMT TO SURFACE. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/20/2014 10:30 AM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

\*\*CASING COLLAPSED AT 1519'. NO RECORD OF ALTERNATE II BEING DONE.  
TOC 2700' ON PRIMARY JOB.\*\* TBG PLACED AT 1510'. PUMP 125 SX CMT &  
CIRCULATE IN 4 1/2' CASING. ANNULUS CHECKED & FILLED WITH 150 SX CMT.  
PRESSURED TO 300#. TOPPED OFF WITH 25 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4354 | 4365 | OH   |          |

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

APR 09 2014

RECEIVED

District: 01

Signed Daniel Sellers  
(TECHNICIAN)

RECEIVED

APR - 3 2014

KCC DODGE CITY