

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-00266-00-01  
Spot: NWNWNE Sec/Twnshp/Rge: 27-34S-2E  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: SCHWARTZ Well #: 1  
County: SUMNER Total Vertical Depth: 3520 feet

Operator License No.: 33918  
Op Name: WELLSTAR CORPORATION  
Address: 11990 GRANT ST STE 550  
NORTHGLENN, CO 80233

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3560		220 SX
SURF	8.625	250		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2013 12:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: FLOYD MCCLASKEY Company: \_\_\_\_\_ Phone: (441) 726-2044

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/20/2013 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:


MAY 2013: MIX AND PUMP 185 SXS 60/40 4% POZ DOWN 4 1/2" CSG. BREAK CIRCULATION WITH 8 5/8" CASING, MIX AND PUMP ANOTHER 160 SXS 60/40 POZ DOWN 4 1/2" CASING. TIE ONTO 8 5/8" AND PUMP 100 SXS CLASS A DOWN SURFACE CASING. USING POLY PIPE DOWN 8 5/8" CASING, PUMP 200 SXS CLASS A ON TOP OF HARD BOTTOM AT 905'. RUN POLY PIPE DOWN 4 1/2' CSG, FOUND HARD BOTTOM AT 290', PUMP 50 SXS CLASS A TO SURFACE. SEPT 2013: REMOVE RAIN WATER FROM WELL'S CELLAR, WELD PLATE ON TOP OF CASING AND FILL IN HOLE WITH CLEAN DIRT.

Perfs:

Remarks:  
Plugged through: CSG

KCC WICHITA  
APR 10 2014  
RECEIVED

District: 02

Signed   
(TECHNICIAN)  
4/17/14