

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-21979-00-00  
Spot: SESWNWSE Sec/Twnshp/Rge: 21-22S-19E  
1550 feet from S Section Line, 1999 feet from E Section Line  
Lease Name: ROOK Well #: 12-8A  
County: ANDERSON Total Vertical Depth: 884 feet

Operator License No.: 30993  
Op Name: M.A.E. RESOURCES, INC.  
Address: PO BOX 304  
PARKER, KS 66072

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	884		
SURF	6.25	21		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/17/2013 12:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: BRAD COOK Company: \_\_\_\_\_ Phone: (913) 898-3221

Proposed Plugging Method: RUN 1" PIPE TO TD. FILL 2 1/2" PIPE TO SURFACE WITH CEMENT - PULL 1" PIPE - SQUEEZE CEMENT WITH PUMP TRUCK.

Plugging Proposal Received By: LARRY MARCHANT WitnessType: NONE  
Date/Time Plugging Completed: 01/17/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH IN 2-INCH CASING AND FILL FROM TD (884 FEET) TO SURFACE.  
HOOK ON TO 2-INCH CASING AND SQUEEZE CEMENT INTO FORMATION AT 300  
PSI, THEN SHUT IN AT 500 PSI. TOTAL OF 40 SACKS CEMENT USED TO PLUG  
WELL.

Perfs:

Top	Bot	Thru	Comments
838	848		

RECEIVED  
APR 09 2014  
KCC Chanute Dist. #3  
LS  
KCC WICHITA

Remarks:

Plugged through: TBG

APR 14 2014  
RECEIVED

District: 03

Signed [Signature]  
4/17/14 (TECHNICIAN)