

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21133-00-00  
Spot: S2SEENENW Sec/Twnshp/Rge: 33-11S-22W  
1210 feet from N Section Line, 2970 feet from E Section Line  
Lease Name: FLAGLER Well #: 9  
County: TREGO Total Vertical Depth: 4090 feet

Operator License No.: 31819  
Op Name: CHOLLA PRODUCTION, LLC  
Address: 10390 BRADFORD RD. SUITE 201  
LITTLETON, CO 80127

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7.875	4088		265 SX
SURF	12.25	316		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2014 10:30 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: KELLY BRANUM Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 483-2662

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Perforations at 3982' - 4000'.  
Shot perforations at 312', 1005', 1825' and 2450'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/02/2014 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3962' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 3060' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1950' and pumped 125 sx cement. Good circulation of cement. Pulled tubing out and topped off w/25 sx cement. Hole standing full. Tied on to back side and squeezed w/15 sx cement. Shut in pressure 350 psi.

GPS: 39.05605 -099.77058

Perfs:

Top	Bot	Thru	Comments
3982	4000		

KCC WICHITA

APR 14 2014


RECEIVED

Remarks: CONSOLIDATED CEMENT TICKET # 44663

Plugged through: TBG

District: 04

Signed

  
4/16/14 (TECHNICIAN)

CM

APR 03 2014