

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21400-00-00
Spot: SW Sec/Twnshp/Rge: 2-32S-43W
1333 feet from S Section Line, 1326 feet from W Section Line
Lease Name: K U Well #: 2-2
County: MORTON Total Vertical Depth: 3504 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2710		WITH 2 SX CMT
CIBP		3270		
PROD	5.5	3500	0	WITH 470 SX CMT
SURF	8.625	1503		WITH 1082 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/26/2014 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 2710' WITH 2 SX CMT. PLUG AT 1530' WITH 30 SX CMT. PLUG AT 450' WITH 30 SX CMT. PLUG AT 60' WITH 15 SX CMT. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: DANIEL SELLERS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2014 3:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CMT CIRCULATED TO SURFACE SET CIBP @ 2710' WITH 2 SX CMT. 1ST PLUG AT 1530' WITH 30 SX CMT. 2ND PLUG AT 450' WITH 30 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT. PUMP 5 SX CMT DOWN BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
3260	3377		
3138	3247		
2985	3105		
2921	2966		
2766	2876		

KCC WICHITA
APR 15 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED

APR - 3 2014

KCC DODGE CITY

Signed

Kenny Sullivan
4/17/14
(TECHNICIAN)