

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-101-22411-00-00
 Spot: NENWSES Sec/Twnshp/Rge: 23-16S-29W
1286 feet from S Section Line, 1875 feet from W Section Line
 Lease Name: DOWELL Well #: 1-23
 County: LANE Total Vertical Depth: 4603 feet

Operator License No.: 3842
 Op Name: LARSON ENGINEERING, INC. DBA LAR
 Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2169		CEMENTED WITH 195 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	5.5	4602	0	WITH 125 SX CMT
SURF	8.625	281		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2014 9:30 AM
 Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
 Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: SAND PERFS TO 4220' & 2 SX CMT. RTIH TO 2220' & CIRCULATE CMT TO 0'. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
 Date/Time Plugging Completed: 03/27/2014 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SANDED PERFS TO 4220' WITH 2 SX CMT. RTIH TO 2220'. LOADED HOLE & CIRCULATED 220 SX CMT TO SURFACE. BACKSIDE HELD TO 300# WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4531	4538		
4264	4272		
4254	4258		

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

APR 15 2014

Plugged through: TBG

RECEIVED

District: 01

RECEIVED

APR - 3 2014

KCC DODGE CITY

Signed

[Signature]
 4/7/14 (TECHNICIAN)

[Handwritten mark]