

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21997-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 1-14S-15W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: DUMLER B Well #: 4  
County: RUSSELL Total Vertical Depth: 3297 feet

Operator License No.: 31431  
Op Name: BARTON EXPLORATION, INC.  
Address: 3017 E 14TH ST  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3294       |             | 175 SX   |
| SURF   | 8.625 | 400        |             | 200 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2014 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: LONNIED BARTON Company: BARTON EXPLORATION Phone: (785) 483-9136

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/26/2014 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 350', 890' and 1450'.  
Ran tubing to 1978'. Had trouble getting down. Pumped 10 BBL of water followed by 100 sx cement w/150 # hulls. Pulled tubing to 1004' and pumped 100 sx cement. Cement circulated. POOH. Hooked to casing and pumped 70 sx cement. Cement circulated out braden head. Shut in.

GPS: 38.85734 -098.93648

Perfs:

Remarks: QUALITY CEMENTING TICKET # 7137

Plugged through: TBG

KCC WICHITA

APR 14 2014

RECEIVED

District: 04

Signed Ray Dinkel  
3/26/14 (TECHNICIAN)

CM