

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21038-00-00
Spot: SESWSE Sec/Twnshp/Rge: 16-34S-2E
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BETZEN Well #: 116
County: SUMNER Total Vertical Depth: 3167 feet

Operator License No.: 3861
Op Name: ENMARK GAS GATHERING L. P.
Address: 17430 CAMPBELL RD STE 230
DALLAS, TX 75252

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2761		
PROD	4.5	2930		150 SX
SURF	8.625	202		175 SX

Well Type: SWD UIC Docket No: D20161.0 Date/Time to Plug: 02/12/2013 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: FLOYD MCCLASKEY Company: Phone: (620) 441-7274

Proposed Plugging Method: SET PLUG ABOVE PERFORATIONS WITH 2 SACKS OF CEMENT ON TOP OF PLUG. PERFORATE BELOW SURFACE CASING AND CEMENT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 02/18/2013 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

GRESSEL OIL FIELD SERVICE: SET CIBP AT 2420' & BAILED 2 SXS CEMENT ON TOP. FILLED CASING WITH WATER. PERF AT 300'. COPELAND ACID & CEMENT: TIED ONTO 4 1/2" CASING & LOADED WITH WATER 2BPM @ 650# CASING PRESSURE. NEVER BROKE CIRCUALTION. HOOKED UP SWEDGE WITH COMP VALVE AND STARTED MIXING CEMENT GOING DOWN HOLE 1.5BPM @ 650#. CIRCUALTED 50 SXS CEMENT (60 40 POZ 4% GEL) TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2825	2827		
2822	2824		
2446	2501		

Remarks: COPELAND ACID & CEMENT

Plugged through: CSG

KCC WICHITA

APR 10 2014

RECEIVED

District: 02

Signed

[Signature]
4/16/14 (TECHNICIAN)
cc to [Signature] 4/16/14

[Signature]