

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20311-00-00
Spot: N2NESESE Sec/Twnshp/Rge: 31-26S-8E
1100 feet from S Section Line, 330 feet from E Section Line
Lease Name: GRAY Well #: 4
County: BUTLER Total Vertical Depth: 2755 feet

Operator License No.: 34185
Op Name: FLINTSTONE ENERGY, LLC
Address: 9647 NE COLE CREEK RD
ELDORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2754	1021	45 SX
SURF	8.625	150		85 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2013 12:00 AM
Plug Co. License No.: 33739 Plug Co. Name: SEK ENERGY, LLC
Proposal Rcvd. from: DOUG LAMB Company: _____ Phone: (620) 432-3404

Proposed Plugging Method: Set CIBP at about 2610'. Install 4 sacks of cement on top of CIBP. Attempt to retrieve casing from about 2300'. Run in cement work string to 250' and pump cement until cement is circulated to surface. Pull tubing and top off well with cement to restore cement plug to surface.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 08/15/2013 12:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

6/19/2013 RIH WITH 87 JOINTS OF 2" TUBING TO 2661' AND PUMPED 24 SXS OF CEMENT. 6/20/2013 TAGGED TOP OF CEMENT PLUG @ 2457' WITH TUBING STRING AND TRIPPED OUT OF HOLE. 7/10/13 SHOT OFF 5 1/2" CASING @ 1020' AND PULLED OUT TO SURFACE. 8/12/2013 RUN IN 9 JOINTS OF 2" TUBING TO 275' AND PUMPED 50 SACKS OF CEMENT FOR A PARTIAL TOP PLUG WHICH DID NOT REACH SURFACE. 8/15/2013 RUN IN 4 JOINTS OF 2' AND HIT CEMENT AT 125'. PUMPED 38 SACKS OF CEMENT TO BRING CEMENT PLUG TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2660	2695		

KCC WICHITA
APR 10 2014

Remarks:

Plugged through: TBG

RECEIVED

District: 02

Signed DUANE KRUEGER
4/16/14 (TECHNICIAN)